DKS *Associates*
TRANSPORTATION SOLUTIONS
1000 Broadway, Suite 450
Oakland, CA 94607
(510)763-2061

Diablo Valley College Transit Center
Bid Sheet

Bid Item No	Ref	Description	Unit	Quantity	Unit Cost	Line Cost
		Civil				
1	01111	Mobilization (up to 5%)	LS	1		
2	01113	Traffic Control	LS	1		
3	01351	Stormwater Pollultion Prevention	LS	1		
4	02210	Earthwork	LS	1		
5	02211	Grind Asphalt Pavement	SF	4611		
6	02110	Site Clearing	LS	1		
7	02370	Sediment Erosion Control Measures	LS	1		
8	02110	Sawcut Pavement	LF	1679		
9	02511	Asphalt Concrete	Ton	606		
10	02514	PCC Paving	SF	**22922**		
11	02231	Aggregate Base	CY	**1000**		
12	02512	Slurry Seal	SF	145804		
13	02510	PCC Curb and Gutter	LF	515		
14	02510	6" PCC Curb	LF	1,875		
15	02510	PCC Sidewalk standard	SF	**1,492**		
16	02510	PCC Curb Ramp w/ Truncated Domes	EA	9		
17	02510	PCC Curb Ramp at Accessible Parking	EA	1		
18	02510	PCC Passageway w/ Truncated Domes	EA	1		
19	02510	PCC Driveway	EA	1		
20	02510	Cobble Stone Paver (Golf Club Road Median)	SF	890		
21	02510	Integral Color Sidewalk	SF	10,738		
22	02510	**Integral Color Pavement (7-inches)**	SF	2,018		
23	02515	Wheel Stop	EA	3		
24	02760	Striping & Pavement Markings (Paint)	LF	13,177		
25	02760	Striping & Pavement Markings (Thermoplastic)	LF	417		
26	02510	Red Curb Paint	LF	867		
27		New Signage	EA	14		
28	01568	Tree Protection (Fence)	LS	1		
29	02720	Drainage Inlet (Type A)	EA	3		
30	02720	Drainage Inlet (Type D)	EA	4		
31	02720	Convert Inlet to Manhole	EA	1		
32	02720	Construct Manhole	EA	1		
33	02720	Install SD Cleanout	EA	1		
34	02720	Adjust Manhole Frame to Grade	EA	2		
35	02720	Storm Drain Pipe 12" RCP	LF	193		
36	02720	Storm Drain Pipe 6" HDPE	LF	58		
37	02700	3/4" PVC SCH 80 Water Line	LF	110		
38	02700	4" PVC **SDR 26** Sanitary Sewer Line	LF	215		
39	02700	3" PVC SCH 40 Conduit (Communication)	LF	56		
40	02700	8" C900 Class 200 PVC Water Main	LF	337		
41	02700	Water Meter	EA	1		
42	02700	Sanitary Sewer Cleanout	EA	**3**		
43	02700	Gas Lateral	LF	65		
44	02700	Backflow Preventer	LS	1		
45	02700	Fire Hydrant	EA	1		
46	02700	Reset Fire Hydrant	EA	1		
47		Relocation of Existing Lighting Parking Lot 8	EA	6		
48		Remove and Salvage Existing Lighting	LS	1		
49		Service Pedestal and electrical installation to point of service	LS	1		
50		New Lighting Transit Center, including shelters	LS	1		
51		Relocate Blue Light Phone	LS	1		
52	02800	Landscaping	LS	1		
53	02850	Underground Irrigation System	LS	1		
54		4-foot Concrete Bench	EA	2		
55		6-foot Concrete Bench	EA	1		
55		Bike Rack	EA	7		
56		Drinking Fountain	LS	1		
57		Trash Receptacles	EA	3		
58		Screen Lattice System	LS	1		
59		Curvilinear Screen Fence	LS	1		
60		Custom Pedestrian Shelters	EA	3		
61		Main Entry Sign	LS	1		
62		Standard Display Case	EA	2		
63		Perimeter Roadway Repair (Allowance)	LS	1	$ 30,000.00	$ 30,000.00
		Base Bid Total				$ -

Bid Alternate #1

Bus Shelter	EA	1			
Bid Alternate Total					$ -
Grand Total					$ -

Bid Alternate #1 Additional Transit Shelter (One). EA 1